

XLP45 Xtra Low Pressure Gas Booster

Technical Specifications

HORSEPOWER 45 HP

PERFORMANCE

Max Suction 15 psig

Max Discharge 35 psig

Max Pressure Boost 20 psig

ENGINE

Model Ford 300 (4.9l)

Usable Compression bhp 48 bhp

BLOWER/COMPRESSOR

Make Gardner Denver

Type Oil-free Screw Compressor

Flow Rates

Inlet Pressure	Discharge Pressure					
	10 PSIG	15 PSIG	20 PSIG	25 PSIG	30 PSIG	35 PSIG
0 PSIG	12.7 e ³ m ³ /d	11.6 e ³ m ³ /d	10.9 e ³ m ³ /d			
1 PSIG	14.2 e ³ m ³ /d	13.0 e ³ m ³ /d	12.0 e ³ m ³ /d			
2 PSIG	15.9 e ³ m ³ /d	14.5 e ³ m ³ /d	13.2 e ³ m ³ /d			
3 PSIG	17.1 e ³ m ³ /d	16.0 e ³ m ³ /d	14.7 e ³ m ³ /d			
4 PSIG	18.7 e ³ m ³ /d	17.5 e ³ m ³ /d	16.2 e ³ m ³ /d			
5 PSIG	20.2 e ³ m ³ /d	18.8 e ³ m ³ /d	17.6 e ³ m ³ /d	16.3 e ³ m ³ /d		
10 PSIG		26.3 e ³ m ³ /d	25.0 e ³ m ³ /d	23.5 e ³ m ³ /d	22.1 e ³ m ³ /d	
15 PSIG			32.8 e ³ m ³ /d	31.5 e ³ m ³ /d	29.5 e ³ m ³ /d	28.2 e ³ m ³ /d

XLP45 Xtra Low Pressure Gas Booster

Installation Requirements

The following information is to provide assistance for the customer in preparing for and ensuring optimal operation of the gas compressor package.

INLET CONNECTION	4" 150#
OUTLET CONNECTION	3" 150#



WELLHEAD CONNECTION	Either hard pipe or flexible hose may be used.
SKID / BUILDING SIZE	Standard Building 7'w x 15'l x 11'h
SKID / BUILDING SIZE	Building with SoundRanger 12'w x 16'l x 11'h
SHIPPING WEIGHT	18,000 lbs

LIFTING

The compressor package must be lifted and placed using a proper lifting device, consisting of a four-point lift (from each corner of the package). The package must remain level during lifting and placement. The unit cannot be skidded and dropped.

ENGINE STARTER

A pneumatic engine starter is provided with the gas compressor package. It requires approximately 60 psig of gas pressure to adequately start the engine.

XLP45 Xtra Low Pressure Gas Booster

MOUNTING SURFACE

The customer is responsible to provide a suitable installation area. The compressor should be mounted on a flat and level bed of packed gravel. The use of planking alone is not recommended. This may cause unlevel settling of the package, unnecessary vibration, and increased sound pressure levels distributed through the skid base.

The gravel pad should extend to sufficient length to support any sound hoods that extend beyond the building walls.



GROUNDING

The compressor package must be grounded. The unit is supplied with a cable lug on skid edge to which the customer is responsible to attach a grounding device. It is recommended that an 8' rod be wired to the grounding lug and inserted into the earth, within 6 feet of the compressor building.

SOUND ATTENUATION

To reduce sound pressure levels cover the exposed surface of the skid base completely with gravel. The compressor package is built with both the cooler and muffler discharge on one side of the package, with the inlet and outlet connections on the other side. Ensure that the package is positioned so that the cooler and muffler discharge (which are the major sources of noise) are directed away from local residence as much as possible.

It is the responsibility of the customer to ensure that the compressor installation meets EUB and regulatory requirements.